

Temporary fencing, (i.e. star picket and orange mesh fence) will prevent damage from uncontrolled or accidental access, or stockpiling during construction.

This will provide protection from machinery and ensure that bulldozers or vehicles do not cross into the planted areas. Temporary fences will be constructed with minimal impact and will be removed after planting has established and the construction work has been completed.

Erection of temporary fencing around perimeter of building envelope and access road needs to be constructed prior to commencement of and building and works.

2.3.2 Permanent fencing of wetlands and remnant vegetation

Permanent fencing shall follow the outer perimeter of any ephemeral wetlands and surround existing remnant vegetation. The proposed layout of permanent fencing is illustrated below.



Figure 2.2 Permanent fencing